

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW-SE-SW

SEC. 5 TWP. 16 RGE. 12-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Depiesse

Operator Mr. Lee Phillips Address #1407 N. Bk. Bldg. Wichita-Kans

Field _____ County Barton

Total Depth 3297 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 5:30 ft. Circulated with cement
5/8" casing set at 3290 ft. & cemented 100 sacks cement.
Plugged back to 2875 ft with chat - dumped
5 sacks of cement at 2875 ft. Chat off & filled the
5/8" casing - mud to 250 ft. Set Rock Bridge &
15 sacks of cement at 250 ft - mud to 30 ft -
Plug to 10 sacks of cement at the surface.

4-14-51

PLUGGING
FILE SEC 5 T 16 R 12W
BOOK PAGE 73 LINE 35

C. W. Stouck
District Conservation Agent
Date 4-APR-1951

CONSERVATION DIVISION
Wichita, Kansas