

46
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

STATE CORPORATION COMMISSION
FEB 7 1963
2-7-63
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name National Cooperative Refinery Assoc.

Complete Address: 305 Rule Bldg., Wichita, Kansas

Lease Name Hofmeister Well No. # 4

Location SW SW NW Sec. 5 Twp. 16 Rge. 12W (E) (W)

County Barton Total Depth 3266

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Shirer Well Servicing Company

Address: Hoisington, Kansas License No. 522

Operation Completed: Hour 5 PM Day 5 Month 2 Year 1963

The Above well was plugged as follows:

8 5/8" 382' Gwc.

Well was plugged back to 2339'. Dumped 5 sax cement with dump bailer.

Pulled pipe. Run 2" tubing to 450'; circulated hole with mud. Pulled

tubing; set bottom plug @ 366' & displaced 25 sax cement. Mud to 40',

set 10' rock bridge, & displaced 10 sax cement, cementing to base of

cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 2/7/63
INV. NO. 10536-W

Signed: John Truman
Well Plugging Supervisor