

15-009-03264-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

SEP 22 1976
9-22-76
Conservation Division
Wichita, Kansas

Operator's Full Name National Cooperative Refinery Ass.

Complete Address Box # 6, Great Bend, Kansas 67530

Lease Name Standinger "A" Well No. 4.

Location NE SW SW Sec. 5 Twp. 16 Rge. (E) (W) 12

County Barton Total Depth 3290'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Plg.

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 4 P Day 21 Month 9 Year 1976

The above well was plugged as follows:

Total Depth 3290' 8 5/8 csg set 513' cwc 225 sx.

5 1/2 csg set 3276' cw 100 sx cem.

5 1/2 csg PBDT 3068' with top perf. (2946')

Filled 5 1/2 csg W/sd (3068'-2920') dumped 5 sx cem W/dump bailer. (2920'-2885')

Cutoff & recovered 1730' of 5 1/2 csg.

Drlg. mud to 270' -set rock & sand bridge (270'-250')

Filled with RMG from 250' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/29/76

INV. NO. 3882-W

Signed: [Signature]
Well Plugging Supervisor