

15-009-03255-00-00
KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 25 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name National Cooperative Refinery Association

Complete Address P. O. Box #6, Great Bend, Kansas 67530

Lease Name Northwest Beaver Unit Well No. 3 -Tract 2

Location NE NW NW Sec. 5 Twp. 16 Rge. (E) (W) 12

County Barton Total Depth 3265'

Abandoned Oil Well Gas Well Input Well XX SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 3:30 P Day 23 Month 7 Year 1974

The above well was plugged as follows:

TD: 3265' 8 5/8 csg set at 335' cwc

5 1/2 csg set at 3261' cw 125 sk.

5 1/2 csg PBD 3257' & perf. (2986')

Filled 5 1/2 csg W/sd (3257'-2950') dumped 5 sk cmt W/dump bailer. (2950'-2915')

Cutoff and recovered 2405' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, released 8 5/8 plug and

pumped 100 sk cmt by Allied Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: L. E. Manning
Well Plugging Supervisor

INVOICED

DATE 7/29/74

INV. NO. 9595-W