

1 051970

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
30 S. Market, Room 2078  
Wichita, KS 67202

10-5

API NUMBER 15- 145-20,977-0000

SW SE SW, SEC. 27, T 21 S, R 15 W/EX

330 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30705

Lease Name Reusch Well # 1

Operator: Younger Energy Company

County Pawnee 127.01

Name & Address 453 S. Webb Rd., Ste. 100

Well Total Depth 3908 feet

Wichita, KS 67207

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 652

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525-0231

Company to plug at: Hour: 1:30 p.m. Day: 5 Month: 10 Year: 1995

Plugging proposal received from Kevin Strube

(company name) D S & W Well Servicing, Inc.

RECEIVED  
STATE CORPORATION COMMISSION  
10-5-95

Work: 4 1/2" at 3907' w/100 sx cement, Perfs at 3902-04'

1st plug sand back to 3850' and dump 4 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 6 sx gel, 100 lbs. hulls,

release 8 5/8" wiper plug and pump 150 sx cement.

CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:30 p.m. Day: 5 Month: 10 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 3850' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down the 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 6 sx gel,

100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2240' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

(If ~~you~~ observe this plugging.

Signed Richard W. Lacy (TECHNICIAN)

DATE 10-30-95

INV. NO. 43895