

15.145.21027-0000 9-23

159

To: 1 120630
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 4/83

S/2 SW NW, SEC. 27, T. 21 S, R. 15 W/E

2970 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6170

Lease Name Bauer Well # 1-27

Operator: Globe Exploration

County Pawnee 129.18

Name & Address P.O. Box 12

Well Total Depth 3975 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 642

Abandoned Oil Well Gas Well Input Well SHD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Great Bend, KS

Company to plug at: Hour: 8:30 a.m. Day: 23 Month: 9 Year: 19 91

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 5 1/2" at 3975' w/125 sx cement, Perfs at 3818-30'

1st plug pump 35 sx common cement with 3% cc,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:30 a.m. Day: 23 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 25 sx cement and displaced with water to 3500',

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-600 psi and shut in 200 psi.

RECEIVED STATE CORPORATION COMMISSION

OCT 01 1991

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2035' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED (old / ~~xxxxxx~~) observe this plugging.

DATE 10-18-91

Signed [Signature] (TECHNICIAN)

INV. NO. 33397