

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-20953-00-00
Spot: CSESWSW Sec/Twnshp/Rge: 27-21S-15W
330 feet from S Section Line, 990 feet from W Section Line
Lease/Unit Name: JOST Well Number: 1
County: PAWNEE Total Vertical Depth: 3905 feet

Operator License No.: 30705
Op Name: YOUNGER ENERGY COMPANY
Address: 453 S. WEBB RD., STE 100
WICHITA, KS 67207

Conductor Pipe: Size feet: \$126.91
Surface Casing: Size 8.625 feet: 618 WITH 300 SX CMT
Production: Size 4.5 feet: 3904 WITH 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/30/2002 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 3840' & 4 SX CMT. 1ST PLUG AT 980' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 650' WITH 50 SX CMT. 3RD PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/30/2002 2:10 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 3896-3900'. SANDED TO 3840' & 4 SX CMT ON TOP WITH DUMP BAILER. PUMPED PLUGS THROUGH CASING. 1ST PLUG AT 980' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 650' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED

MAY 03 2002

KCC WICHITA

5-3-02

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2033' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

INVOICED

MAY 01 2002

DATE 5-6-02

INV. NO. 2002061737

Form 0-278


