

To: 1 090157  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1-13-92  
API NUMBER 15- 145-21,387-0000  
125' W of  
SE NE SE, SEC. 30, T. 21 S, R. 15 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 6588

1650 feet from S section line

455 feet from E section line

Lease Name Unruh Well # 1

County Pawnee 126.75

Well Total Depth 3900 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 938

Operator: Woodman-Iannitti Oil Co. &  
Name &  
Address Pate-Dombaugh, Inc.  
P.O. Box 308  
Great Bend, KS 67530-0308

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Woodman-Iannitti Drilling Company License Number 5122

Address P.O. Box 308, Great Bend, KS 67530-0308

Company to plug at: Hour: 8 p.m. Day: 13 Month: 1 Year: 19 92

Plugging proposal received from Rich Wheeler

(company name) Woodman-Iannitti Drilling Co. (phone) 316-792-1922

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 928-63'

1st plug at 970' with 80 sx cement,

2nd plug at 470' with 50 sx cement,

3rd plug at 40'.with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 10:30 p.m. Day: 13 Month: 1 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 970' with 80 sx cement,

2nd plug at 470' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

**RECEIVED**  
KANSAS CORPORATION COMMISSION

JAN 16 1992 1-16-92

CONSERVATION DIVISION  
WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services.  
(if additional description is necessary, use BACK of this form.)

**INVOICED**  
observe this plugging.

DATE FEB 10 1992

Signed [Signature]  
(TECHNICIAN)

INV. NO. 34447

FOR KCC USE:

P.4.

FORM C-1 7/91

EFFECTIVE DATE: 12-2-91

State of Kansas 15-145-21,387.0000

FORM MUST BE TYPED

DISTRICT # 1  
SEAT: Yes No

NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date Dec 1 1991  
month day year

Spot 125' West of East  
SE-NE-SE Sec 30 Twp 21 S Rg 15 West

OPERATOR: License # 6588  
Name: Woodman-Iannitti Oil Co. & Pate-Dombaugh, Inc.  
Address: P.O. Box 308  
City/State/Zip: Great Bend, KS, 67530-0308  
Contact Person: Dick J. Iannitti  
Phone: 316-792-1922

1650 feet from South / North line of Section  
455 feet from East / West line of Section  
IS SECTION REGULAR IRREGULAR?  
(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Pawnee

CONTRACTOR: License # 5122  
Name: Woodman-Iannitti Drilling Co.

Lessee Name: Haruh Well #: 1  
Field Name: Wildcat JAC  
Is this a Prorated/Spaced Field? yes X no  
Target Formation(s): Arbuckle  
Nearest lease or unit boundary: 455  
Ground Surface Elevation: 1973 est. feet MSL

Well Drilled For: Well Class: Type Equipment:  
X Oil Enh Rec Infield X Mud Rotary  
Gas Storage Pool Ext. Air Rotary  
OWWO Disposal X Wildcat Cable  
Seismic: # of Holes Other

Water well within one-quarter mile: yes X no  
Public water supply well within one mile: yes X no  
Depth to bottom of fresh water: 100  
Depth to bottom of usable water: 300 370  
Surface Pipe by Alternate: X 1 2  
Length of Surface Pipe Planned to be set: 960  
Length of Conductor pipe required: None

If OWWO: old well information as follows:  
Operator:  
Well Name:  
Comp. Date: Old Total Depth

Projected Total Depth: 4000  
Formation at Total Depth: Arbuckle  
Water Source for Drilling Operations:  
well farm pond X other

Directional, Deviated or Horizontal wellbore? yes X no  
If yes, true vertical depth:  
Bottom Hole Location:

DWR Permit #:  
Will Cores Be Taken?: yes X no  
If yes, proposed zone:

AFFIDAVIT

390' Alt. I Req.

Exp. 5/27/92

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.  
It is agreed that the following minimum requirements will be met.

Pusher Rich Wheeler 387  
SPUD DATE 1-7-92 INIT. SM  
LENGTH SURFACE PLANNED 960 85B

RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 85B @ 938 CONDUCTOR  
ANHYDRITE T- 938 B- 963 ELEVATION

TD 3900 FORMATION Ark.

RAN PIPE @ DV TOOL ALT II DONE  
SX Y N

Arbuckle Plug @ Ft. W/ SX

Hug./Council @ Ft. W/ SX

Anhydrite Base @ 970 Ft. W/ 80 SX

1/2 Base Anyh. @ 470 Ft. W/ 50 SX

1/2, 1/2 Plug @ Ft. W/ SX

Bottom Surface @ Ft. W/ SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W SX MOUSE HOLE W/ SX

WATER WELL Fiberglass (Irr. Well Pond Hauling)

TECHNICIAN Sam DATE 1-13-92

TYPE OF CEMENT 60/40 67b

STARTING TIME 8:00 AM DATE 1-13-92

COMPLETION TIME 10:30 AM DATE 1-13-92

CEMENT COMPANY B.J.