

8-24

4-060432

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-009-23,887 0000

NE NE SW /4 SEC. 08, 16 S, 12 W  
2310 feet from S section line  
2970 feet from E section line

Operator license# 6039 Lease Luerman well # 2

Operator: L.D. Drilling, Inc. County Barton

Address: R.R. 1 - Box 183B Well total depth 3370 feet 109.52  
Great Bend, Kansas 67530 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 334 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pullers, Inc. License# 6050

Address: P.O. Box 347 - Chase, Kansas 67524

Company to plug at: Hour: 9:00A.M. Day: 24 Month: August Year: 93

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pullers, Inc. Phone: 316-938-2943

Were: Order 200 sxs. 60/40 posmix - 10% gel and hulls.  
Plug while pulling casing.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 12:30P.M., Day: 24, Month: August, Year: 93

Actual plugging report: 8 5/8" to 334'. 5 1/2" to 3369'. Sand back to  
3250' and spot 5 sxs. cement with dump bailer. Shot casing at 2500'  
and pulled to 1660'. Pumped 90 sxs. cement with 100# hulls. Pulled  
casing to 830' and pumped 25 sxs. cement. Pulled casing to 450' and  
circulated cement with 85 sxs. cement and 100# hulls. 9-13-93

RECEIVED  
STATE CORPORATION COMMISSION

SEP 13 1993

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO   
Bottom plug(in place): YES  CALC , NO  Dakota plug: YES  NO   
Plugged through TUBING , CASING . Elevation: 1874 GL

I did  did not  observe the plugging.

Bert Jones  
PK (agent)

INVOICED

SEP 14 1993

DATE 38626  
INV. NO. 38626