

6-16-88 219 R

To: 6 070689
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009-03261-00-00
SE SW SW, SEC. 5, T 16 S, R 12 W 1

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565

feet from S section line
feet from E section line
NW Beaver
Lease Name taudinger Well # T 9 W 1

Operator: National Cooperative Refinery Asso
Name & Address Box 6
Great Bend, Ks. 67530
I. J. Gotsike

County Barton 106.83
Well Total Depth 3287 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 545

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing Co. License Number

Address Box 31 Russell, Ks. 67665

Company to plug at: Hour: 10:00 AM Day: 16 Month: June Year: 19 88

Plugging proposal received from Jim Rockhold and Jim Baker

(company name) Rockhold Eng. and NCRA (phone)

were: 8 5/8" 545' S.P. cwc w/275 sks. 5 1/2" casing set at 3287' w/

Perfs at 3039' - 43' to 3063' - 70'; at bottom sand to 2980' and w/5 sks cement.

Shot casing 3 times, recovered 1616'; Proposal 140 sks 65/35 Poz 10% Gel and 2%

Additive and 5 sks Hulls. Pump in 8 5/8" S.P. 25 sks cement; followed with 115 sks

cement w/5 sks Hulls added in. Shut in under pressure.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:00 AM Day: 16 Month: June Year: 19 88

ACTUAL PLUGGING REPORT Ordered 140 sks 65/35 Poz 10% Gel 2% Additive and 5 sks Hulls.

Pumped in with pump truck. Pumped in 25 sks cement followed with 115 sks cement with

5 sks Hulls added in. Max pressure 300 Psig. Shut in at 100 Psig. Cemented by Allied

Cement.

RECEIVED
STATE CORPORATION COMMISSION
7-6-88
JUL 6 1988

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

DATE 7-13-88

INV. NO. 21283

6-16

AUG 3 1988

Signed Marion J. Schmidt (TECHNICIAN)