

4-010437

D-17,923

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-20419-00-01

SE NW NE /4 SEC. 05, 16 S, 12 W
4290 feet from S section line
1650 feet from E section line

Operator license# 4871

Lease: Hilgenberg Well# 2

Operator: Curt's Oil Operations

County: Barton 11/2.06

Address: Box 8
Great Bend, Kansas 67530

Well total depth 3448 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 577 feet

Aband. oil well Gas well Input well SWD X, D & A

Plugging contractor: D.S. & W. Well Servicing License# 6901

Address:

Company to plug at: Hour: 10:00 A.M. Day: 26 Month: January Year: 2000

Plugging proposal received from: Curtis Hitschman

Company: Curt's Oil Operations Phone: -

Were:

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 11:00 A.M. Day: 26 Month: January Year: 2000

Actual plugging report: Tied onto 5 1/2" and pumped 50 sxs 60/40 pozmix - 10% gel cement with 300# hulls followed by 21 sxs gel with 200# hulls, followed by 80 sxs cement with 200# hulls. Pumped 50 sxs cement with 100# hulls down backside. Max. P.S.I. 400#. S.I.P. 100#.

Remarks:

Condition of casing(in hole): GOOD BAD Any plug: YES NO
Bottom plug(in place): YES CALC NO Dakota plug: YES NO
Plugged through TUBING CASING X Elevation: GL

I did [X] / did not [] observe the plugging. Cora Morris

(agent)

INVOICED

DATE 2/4/00

INV. NO. 061219

RECEIVED Form CP-2/3
STATE CORPORATION COMMISSION

2-4-00
FEB - 4 2000

CONSERVATION DIVISION
Wichita, Kansas