

10-22
28
R
4-041412

15-009-02101-0000

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1942

S2 SE SW /4 SEC. 05, 16 S, 12 W
330 feet from S section line
3300 feet from E section line

Operator license# 5552

Lease Stull well # 1

Operator: Gore Oil Company

County Barton

Address: 202 S. St. Francis
Box 2757
Wichita, Kansas 67202

Well total depth 3180 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 327 feet
cmt. N/A

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Halliburton Cementing License# -

Address: Great Bend, Kansas 67530

Company to plug at: Hour: 8:00 A.M. Day: 22 Month: October Year: 92

Plugging proposal received from: Scott Shermaner

Company: Gore Oil Company

Phone: 316-263-3535

Were: 5 1/2" casing set @ 3179' w/ 150 sx. cement. Perf. @ 2968' -
3135'. Order 375 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus
600# hulls.

Plugging Proposal Received by: Dennis L. Hamel (Gib Scheck)

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:30 P.M., Day: 22, Month: October, Year: 92

Actual plugging report: Run in hole with tubing to 2600'. Spot 75 sx.
cement w/200# hulls mixed in cement. Pull tubing to 1500'. Spot 75 sx.
cement w/200# hulls mixed in cement. Pull tubing to 820'. Spot 100 sx.
cement w/100# hulls in cement to circulate at surface. Hooked-up to
5 1/2" casing squeezed 85 sx. cement. Max. P.S.I. 1000#. S.I.P. 300#.
Hooked-up to 8 5/8" S.P. squeezed in 40 sx. cement. Max. P.S.I. 500#.
S.I.P. 300#.

Remarks:

Condition of casing(in hole): GOOD BAD X Any plug: YES X NO NOV 12 1992
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING. Elevation: GL

I did X y did not] observe the plugging.

Dennis L. Hamel

DATE

11-23-92

INV. NO.

36852

(agent)

Form CP-2/3