

9-12-15-009-19327-0000

To: 6 061664
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- E-14,582
SW, SEC. 5, T 16 S, R 12 W/EX
2310 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565

Lease Name NW Beaver Well # T 10-W1
County Barton 107.06

Operator: National Cooperative
Name & Address Refinery Assoc. Box 6
Great Bend, Ks. 67530

Well Total Depth 3294 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 330

Abandoned Oil Well Gas Well Input Well X SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 10:00AM Day: 12 Month: Sept Year: 19 88

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone)

were: Order 200 sks 60/40 Poz 8% Gel 3% Cal Cl. 5 sks Hulls.

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1988
CONSERVATION DIVISION
Wichita, Kansas

rcw
09-16-88

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:00AM Day: 12 Month: Sept Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 330' w/cwc. 5 1/2" set at 3130' w/100 sks.

Top perf at 2876'. Plugged bottom w/sand and 5 sks cement to 2850'. Shot pipe

four times and recovered 1500'. Pumped in 8 5/8" 25 sks cement followed w/5 sks

Hulls in 175 sks cement w/800 psi. Ran line to 1000'.

Remarks: By Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (and my successors) observe this plugging.

DATE 9-22-88

INV. NO. 22372

Signed [Signature] (TECHNICIAN)