

6 060221

15-009-15700-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

SE, SEC. 8, T 16 S, R 12 W

1650 feet from W/S section line

330 feet from E/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7062

Lease Name Felton Well # 7

Operator: Keener Oil Co.

County Barton

Name & Address 320 South Boston #406

Well Total Depth 3294 109.06 feet

Tulsa, Ok. 74103

Conductor Pipe: Size _____ feet

Surface Casing: Size 7" feet 356'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Haliburton Services License Number _____

Address Great Bend, Ks. 67530

Company to plug at: Hour: 2:00PM Day: 10 Month: May Year: 19 84

Plugging proposal received from Harry Sharon

(company name) Keener Oil Co. (phone) 716-532-3848

were: Order 150 sh. 50 pos mix - 6 7/8" gel - 3 3/4" gel, 15 sh. gel, 4 sh. balls & 5 1/2" plug

Plugging Proposal Received by Arthur J. Schul
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:00PM Day: 10 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 7" set at 356' cwc. 5 1/2" set at 3294' w/ 300 sh.

Squeezed at 2468' to surface w/ 500 sh. Plug back to 2985'

Top perf at 2985'. Pumped in 7" 65 sh. cement w/ 300 pounds pressure.

Pumped in 5 1/2", 25 sh. cement, 4 sh. balls, 15 sh. gel, released plug & followed

w/ 60 sh. cement w/ 400 pounds pressure.

Remarks: By Haliburton

(if additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

DATE 5-31-84

INV. NO. 1757

Signed Arthur J. Schul
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
MAY 29 1984
CONSERVATION DIVISION
Wichita, Kansas

5-10 JUN 04 1984