

State of Kansas



15-145-20483-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1977
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Deist of B&N Drlg. has this
date requested permission to plug the following described well:

Mr. De ist guarantees payment of the plugging fee.

Operator's full Name: BMG, Inc.

Complete Address: 1400 Metrobank Bldg., Denver, Colo.

Lease Name: Unruh Well No. 1

Location: C SW SE Sec. 30 Twp. 21 Rge. (E)(W) 15

County: Pawnee Total Depth 3909' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Deist was instructed to plug the well as follows:

Run pits, circulate heavy mud, set 50 sk cmt plug at 660' thru drill
pipe. Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy
mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Mussey
Conservation Division Agent