



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 25 1972  
08-25-72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Morton Specter of Specter Pipe & Supply, Inc. has this  
date requested permission to plug the following described well:

Mr. Morton Specter guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe & Supply, Inc.

Complete Address: Box 169, Russell, Kansas 67665

Lease Name: Bushnell "B" Well No. # 2

Location: NW SW NE Sec. 8 Twp. 16 Rge. 12 (E)(W) W

County: Barton Total Depth 3293 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Ralph Lynch was instructed to plug the well as follows:

12" csg. 48' wh/75 sax cement. 8 5/8" csg. 595' Cwc.

Sanded hole back to 3050' & dumped 5 sax cement with dump bailer.

Pulled pipe. Squeezed well with 15 sax mud, plug, & 100 sax cement  
with pump truck, cementing from 340' to base of cellar.

Very truly yours,

Don L. Linn  
Conservation Division Agent