

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

FEB 7 1963
 2-7-63
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Robert Faris of National Cooperative Ref has this

date requested permission to plug the following described well:

Mr. Ralph Booker guarantees payment of the plugging fee.Operator's full Name: National Cooperative Refinery Assoc.Complete Address: 305 Rule Building, Wichita, KansasLease Name: Hofmeister Well No. # 4Location: SW SW NW Sec. 5 Twp. 16 Rge. 12W(E) (W)County Barton Total Depth 3266 Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Robert Faris was instructed to plug the well as follows:8 5/8" 382' Cwc.

Well was plugged back to 2339'. Dumped 5 sax cement with
dump bailer. Pulled pipe. Run 2" tubing to 450'; circulated
hole with mud. Pulled tubing; set bottom plug @ 366' &
displaced 25 sax cement. Mud to 40', set rock bridge; &
displaced 10 sax cement, cementing to base of cellar.

Very truly yours,

Law Truman
 Conservation Division Agent