

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH


Locate well correctly on above  
Section Plat

Pawnee County, Sec. 2 Twp. 21 Rge. 16 (E) (W)  
Location as "NE/CNW/SW" or footage from lines SE SE NW  
Lease Owner Honaker-Davis Drlg. Co.  
Lease Name Lewis Well No. 1  
Office Address 2008 Lakin, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 7-11 19 56  
Application for plugging filed 7-10 19 56  
Application for plugging approved 7-10 19 56  
Plugging commenced 7-11 2:30 A.M. 19 56  
Plugging completed 7-11 4:00 A.M. 19 56  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Brundge, Hoisington, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 3832 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1027	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to 300' with heavy rotary mud. Put in 1/3 sacks of hulls ahead of plug at 300'. Mixed 20 sacks cement through drill pipe. Filled hole to 35' with rotary mud. Dumped 1/3 sack hulls ahead of plug. Cemented with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor  
Address

STATE OF KANSAS, COUNTY OF BARTON, ss.  
R. T. Ellison (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

*R. T. Ellison*

Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 11th day of July, 19 56

Kenneth G. Fischer Notary Public.

My commission expires 6-25-59

7-14-56

PLUGGING

FILE SEC. 2 T. 21 R. 16W

BOOK PAGE 99 LINE 30


DRILLERS LOG

Lewis No. 1  
 Loc: SE SE NW  
 Sec: 2-21-16  
 Pawnee County, Kansas  
 Company: Honaker-Davis Drilg. Co., et al  
 Contractor: Honaker-Davis Drilg. Co.


Comm: 6-29-56  
 Comp: 7-11-56  
 Rotary Total Depth: 3832  
 Casing: 3-5/8" at 1027  
 D & A

0	45	Surface soil & clay	
45	200	Clay	
200	290	Shale & Clay	
290	445	Blue Shale	
445	557	Sand	
557	625	Shale & Shells	
625	1017	Red Bed & Shale	8-5/8" casing cemented at
1017	1042	Anhydrite	1027' with 525 sacks cement
1042	1535	Shale & Shells	and 5 sacks calcium chloride
1535	1765	Shale, Shells & Salt	
1765	1790	Shale & Anhydrite	
1790	2210	Lime & Shale	
2210	2280	Lime & Shale Streaks	
2280	2300	Shale & Lime	
2300	2355	Lime & Shale	
2355	2805	Shale & Lime	
2805	2875	Lime & Shale Streaks	
2875	3330	Lime & Shale	
3330	3380	Lime	
3380	3470	Lime & Shale	
3470	3720	Lime	
3720	3738	Lime & Chert	
3738	3786	Simpson Shale	
3786	3832	Arbuckle	
3832		Total Rotary Depth	D & A

I certify that this is the true and correct copy of  
 the above log to the best of my knowledge.

  
 H. S. Forbes

Subscribed and sworn to before me this 12th day of  
 July, 1956.

  
 Kenneth G. Fischer, Notary Public

My commission expires: 6-25-59

PLUGGING			
FILE	SEC	T 21	R 160
BOOK	PAGE	29	LINE 30