

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH

Locate well correctly on above
Section Plat

Pawnee County, Sec. 2 Twp 21s Rge. (E) 16 (W)
Location as "NE/CNW&SW" or footage from lines. SE SE NE
Lease Owner Braden Deem Inc.
Lease Name Kindsvater Well No. 1
Office Address 200 E. First ST. Wichita Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 10-51
Application for plugging filed 5-7 19 74
Application for plugging approved 5-8 19 74
Plugging commenced 5-23 19 74
Plugging completed 5-29 19 74
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 11-10 19 73
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Arbuckle Depth to top 3795 Bottom 3805 Total Depth of Well 3805 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	1015	8 5/8		
		0	3795	5 1/2		2771

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Filled with sand to 3780 then dumped 4 sx. cement
Hole filled to 450 ft. with water bridged to 420 ft. filled to
bottom of cellar with 6 yards of readymix cement

10-5-74

RECEIVED
STATE CORPORATION COMMISSION
JUN 5 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Nicholas Casing Pulling
Address Box 373 Geneseo Kansas

STATE OF Kansas COUNTY OF Rice, ss.
George A. Nicholas (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Nicholas

Subscribed and Sworn to before me this 4th day of June 19 74

My commission expires Sept. 24, 1974
Waverly Hargrett Notary Public.


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ALPINE OIL & ROYALTY CO., INC.
Farm- Sam Kindsvater No. 1

SEC. 2 T. 21 R. 16W
SE SE NE

Total Depth. 3805'
Comm. 2-25-63 Comp. 3-7-63
Shot or Treated.
Contractor. Quaker Drilg. Co., Inc.
Issued. 7-13-63

County Pawnee
KANSAS



Elevation. 1996' KB

Production. 30.89 BOPD, NW

CASING:

8 5/8" 1015' cem w/475 sk.
5 1/2" 3795' cem w/150 sk.

Figures Indicate Bottom of Formations.

yellow clay & shells	200
hard sand	203
shale & shells	335
shale	430
Dakota sand	550
hard sand	600
red bed & shale	1006
anhydrite	1035
shale & shells	1665
lime & shale	2500
shale & shells	2660
lime & shale	3060
lime	3450
lime & shale	3520
lime	3660
lime & shale	3725
cherty lime & shale	3760
lime	3795
arbuckle	3805 RTD
Total Depth	

TOPS:

Anhydrite (Sample)	
Heebner	3345
Brown Lime	3439
Lansing	3450
Base Kansas City	3684
Viola	3710
Simpson	3753
Arbuckle	3786

RECEIVED
STATE CORPORATION COMMISSION
MAY 8 - 1974
CONSERVATION DIVISION
Wichita, Kansas