

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-145-21,312-0000

LEASE NAME Mermis

TYPE OR PRINT

NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1-2

3630 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 2 TWP. 21 RGE. 16 (E) or (W)

COUNTY Pawnee

Date Well Completed 1-27-90

Plugging Commenced 1-27-90

Plugging Completed 1-27-90

LEASE OPERATOR Dominion Oil & Gas Corp.

ADDRESS 107 North Market, Suite 1115 Wichita, KS 67202

PHONE# (316) 267-7551 OPERATORS LICENSE NO. 30224

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-26-90 (date)

by Mike Spain (KCC District Agent's Name).

Is ACO-1 filed? to be filed by operator if not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3900

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 3800' w/40 sacks cement thru drill pipe
 Next Plug: @ 1070' w/50 " " " " " " 15 sacks in Rat Hole
 Next Plug: @ 550' w/50 " " " " " " 15 sacks in Water Well
 Top Plug: @ 40' w/10 " " " " " "

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Jay Schneider (Employee of Operator) or Operator of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Jay D. Schneider

(Address) P.O. Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 5th day of February, 19 90

Dorothy M. Hogue
 Notary Public

My Commission Expires: 5-5-90



2-790
 RECEIVED
 STATE CORPORATION COMMISSION
 FEB 7 1990
 CONSERVATION DIVISION
 Wichita, Kansas

DRILLER'S WELL LOG

DATE COMMENCED: Janaury 19, 1990
DATE COMPLETED: Janaury 27, 1990

Dominion Oil & Gas Corp.
MERMIS #1-2
NE SW NE
Sec. 2, T21S, R16W
Pawnee County, Ks.

0 - 130' Surface Soil, Sand, Shale
130 - 419' Lime & Shale
419 - 557' Sand
557 - 1015' Shale
1015 - 1041' Anhydrite
1041 - 1405' Shale & Lime
1405 - 3107' Lime & Shale
3107 - 3756' Shale & Lime
3756 - 3900' Dolomite
3900' RTD

ELEVATION: 2003 K.B.

Surface Pipe: Set new
8-5/8" 23# pipe @1041.5'
w/375 sacks 60/40 pozmix
2% gel 3% cc.

A F F I D A V I T


STATE OF KANSAS
COUNTY OF BARTON) ss:

Jay Schneider of lawful age does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Jay D. Schneider

Subscribed and sworn to before me this 5 day of February 1990.

Dorothy M. Hague
Notary Public



RECEIVED
STATE OF KANSAS COMMISSION
FEB 7 1990
CONSERVATION DIVISION
Wichita, Kansas