


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Pawnee County. Sec. 9 Twp. 21 Rge. 16W (E) (W)  
Location as "NE/CNW%SW%" or footage from lines NW NW SE  
Lease Owner McKnab Production Company, Inc.  
Lease Name Wedel Well No. 1  
Office Address Mile High Center, Denver, Colorado  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-11 19 59  
Application for plugging filed 5-11 19 59  
Application for plugging approved 5-11 19 59  
Plugging commenced 5-11 19 59  
Plugging completed 5-11 19 59  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3882 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO   | SIZE  | PUT IN | PULLED OUT               |
|-----------|---------|------|------|-------|--------|--------------------------|
|           |         | 0    | 1002 | 8-5/8 | 1002   | none - cement circulated |
|           |         |      |      |       |        |                          |
|           |         |      |      |       |        |                          |
|           |         |      |      |       |        |                          |
|           |         |      |      |       |        |                          |
|           |         |      |      |       |        |                          |
|           |         |      |      |       |        |                          |
|           |         |      |      |       |        |                          |
|           |         |      |      |       |        |                          |
|           |         |      |      |       |        |                          |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug set at 300', 20 sacks cement  
Plug set at 40', 10 sacks cement to surface

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 14 1959  
CONSERVATION DIVISION  
Wichita, Kansas  
5-14-59

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Mallonee Drilling Company, Inc.  
Address 820 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
F. W. Mallonee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. W. Mallonee  
820 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of May, 19 59

My commission expires December 14, 1961  
Martha Dwyer Notary Public.

PLUGGING  
FILE SEC 9 T. 21 R. 16W  
BOOK PAGE 39 LINE 4

DRILLERS' LOG

#1 Wedel  
NW. NW SE Section 9-21S-16W  
Pawnee County, Kansas

OPERATOR: McKnab Production Company, Inc. COMMENCED: 4-27-59  
CONTRACTOR: Mallonee Drilling Company, Inc. COMPLETED: 5-11-59

D & A

| FROM | TO   | DESCRIPTION            | CASING RECORD  |            |
|------|------|------------------------|--|------------|
| 0    | 40   | Surface clay           | 8-5/8" surface casing set at 1002' with 475 sacks cement, 2 CC |            |
| 40   | 240  | Sand and shale         |  |            |
| 240  | 530  | Sand                   |  |            |
| 530  | 715  | Shale and shells       |  |            |
| 715  | 980  | Shale, shells, red bed |  |            |
| 980  | 999  | Red bed                |  |            |
| 999  | 1002 | Anhydrite              | Elevation:   | 1998 R.B.  |
| 1002 | 1030 | Anhydrite              | Heebner  | 3388 -1390 |
| 1030 | 1935 | Shale and shells       | Toronto  | 3409 -1411 |
| 1935 | 2005 | Shale and lime         | B/Oread  | 3422 -1424 |
| 2005 | 2095 | Shale and lime shells  | Brown Lime   | 3479 -1481 |
| 2095 | 2185 | Lime                   | Lansing  | 3489 -1491 |
| 2185 | 2490 | Shale and lime         | Base K.C.  | 3729 -1731 |
| 2490 | 2640 | Shale and lime shells  | Marmaton   | 3748 -1750 |
| 2640 | 2775 | Shale and lime         | Conglomerate   | 3774 -1776 |
| 2775 | 2925 | Shale and lime shells  | Viola  | 3788 -1790 |
| 2925 | 3530 | Lime and shale         | Simpson  | 3811 -1813 |
| 3530 | 3560 | Lime                   | Arbuckle   | 3839 -1841 |
| 3560 | 3882 | Lime and shale         | R.T.D.   | 3882 -1884 |
| 3882 |      | Rotary Total Depth     |  |            |

I hereby certify that the above is a true and correct Drillers' Log of the captioned well, to the best of my knowledge and belief.

F. W. Mallonee  
F. W. Mallonee

State of Kansas )  
                          ) ss.  
County of Sedgwick )

Subscribed and sworn to before me this 13th day of May, 1959.

My commission expires:  
December 14, 1961

Martha Gorges  
Notary Public (Martha Gorges)

PLUGGING  
FILE SEC 9 T.21 R.16W  
BOOK PAGE 39 LINE 4