

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County. Sec. 4 Twp. 21<sup>S</sup> Rge. (E) 16 (W)

Location as "NE/CNW%SW%" or footage from lines NE SE NW

Lease Owner Arvel C. Smith

Lease Name Nelson Well No. #1

Office Address 569 Strafford, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 2/7/62 19

Application for plugging filed 2/7/62 19

Application for plugging approved 2/7/62 19


Plugging commenced 2/7/62 19

Plugging completed 2/7/62 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well W. L. Lackamp, Stafford, Kansas.

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st plug set @1000' W/30 sacks cement, 1/4 sack Hulls,  
2nd plug set @300' W/20 sacks cement, 1/4 sack Hulls, 3rd plug set @40'  
W/10sacks cement, 1/4 sack Hulls, 2 sacks cement dry in Rat Hole.  
Plugging complete @7:30 AM, 2/7/62

RECEIVED  
FEB 10 1962  
CONSERVATION DIVISION  
Wichita, Kansas

2-20-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Wilkinson Drilling, Inc.

Address 805 Union Center, Wichita 2, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Walter M. Wilkinson (employee of owner or owner or operator)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter M. Wilkinson  
805 Union Center, Wichita 2, Kansas.  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of February, 1962

My commission expires January 2, 1965  
Carolyn K. Iverson Notary Public.



15.145.00456.0000

15.145.00456.0000

WILKINSON DRILLING, INC.

805 UNION CENTER  
WICHITA 2, KANSAS

February 16, 1962

DRILLERS LOG

Arvel C. Smith  
Nelson #1

NE SE NW Sec. 4-21S-16W  
Pawnee County, Kansas.

Contractor:	Wilkinson Drilling, Inc.
Commenced:	January 28, 1962
Completed:	February 7, 1962
Elevation:	2000 DF
Surface Casing:	8 5/8" @ 1014' w/200 sx.sunset & 250 sx.common
Total Depth:	3845'

FIGURES INDICATE BOTTOMS OF FORMATIONS:

<u>Depth</u>	<u>Formation</u>
0 - 350	Surface sands and clay
350 - 623	Clay
623 - 905	Shaled red bed
905 - 1008	Shale and red beds
1008 - 1040	Anhydrite
1040 - 1880	Shale and shells
1880 - 2425	Lime
2425 - 2690	Lime and shale
2690 - 2840	Shale and lime
2840 - 3105	Lime and shale
3105 - 3162	Lime
3162 - 3249	Shale and lime
3249 - 3380	Lime
3380 - 3437	Shale
3437 - 3665	Lime and shale
3665 - 3738	Shale and lime
3738 - 3786	Shale and sand
3786 - 3845	Arbuckle dolomite

**RECEIVED**  
STATE CORPORATION COMMISSION  
FEB 20 1962  
CONSERVATION DIVISION  
Wichita, Kansas

We hereby certify the above and foregoing to be a true and correct copy of the driller's log on the Nelson #1, located in the NE SE NW of Section 4-21S-16W, Pawnee County, Kansas

WILKINSON DRILLING, INC.

*Walter M. Wilkinson*  
Walter M. Wilkinson, President

Subscribed and sworn to before me this 16th day of February, 1962.

*Carolyn K. Iverson*  
Carolyn K. Iverson, Notary Public

My commission expires: January 2, 1965.