

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-23,887 0000

LEASE NAME Luerman

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 8 TWP. 16 RGE. 12W (E) or (W)

COUNTY Barton

Date Well Completed

Plugging Commenced 8-20-93

Plugging Completed 8-24-93

LEASE OPERATOR L. D. Drilling, Inc.

ADDRESS RR1, Box 183B, Great Bend, KS 67530

PHONE# (316) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Hubert Deines (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3370'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 334' | none |
| | | | | 5 1/2" | 3369' | 2501' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sanded bottom to 3223' & 5 sks cement. Shot @ 2609', worked pipe. Shot @ 2501', worked pipe free, pulled 20 joints. Pumped 90 sks @ 1650' w/200# hulls. Pumped 25 sks @ 830' w/100# hulls. Circulated cement to surface @ 450' w/85 sks & 100# hulls 60/40 pos 10 % gel Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. D. Drilling, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 25th day of August AUG 26, 1993

Jane Herzberg
Notary Public CONSERVATION DIVISION
Wichita, Kansas

My Commission Expires:

