

15-009-23257-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Barton SEC. 8 TWP. 16 RGE. 12 E/W
 Location as in quarters or footage from lines:
330' from south line, 2310' from west line

Lease Owner L. D. Davis/ L. D. Drilling, Inc.
 Lease Name Luerman Well No. 1
 Office Address Route 1, Box 183-B, Great Bend, Kansas 67530
 Character of Well (Completed as Oil, Gas or Dry Hole): oil
 Date Well Completed 10/08/83
 Application for plugging filed 04-12-85
 Plugging commenced 04-15-85
 Plugging completed 04-25-85
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Plat.

non productive
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck
 Producing formation Topeka Depth to top 2950' bottom 3389' T.D. 3390'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	Surface	0	319	8 5/8"	319	0
	Production	0	3389	5 1/2"	3389	2250

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Dumped 5 sacks of cement on Halliburton plug, set at 2840'. Melex shot pipe
at 2450', pipe would not come, shot at 2354', could not pull, shot at 2250',
pulled 57 joints of 5 1/2" casing.

04-25-85 Halliburton dumped 4 sacks of hulls, 25 sacks of cement, 12 sacks of
gel, 40 sacks cement, 3 sacks gel, 1 sack hulls. Pull in wiper plug 8 5/8",
100 sacks of cement, maximum pressure 1700, shut in pressure 1250.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D. S. & W. Well Servicing, Inc. operator No. 6901


STATE OF Kansas COUNTY OF Barton ss.
L. D. Davis (~~XXXXXXXXXXXX~~) or (~~XXXXXXXX~~) operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) L. D. Davis
Great Bend, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of May, 19 85

My Commission expires: 5-20-85

Bessie M. DeWerff
 Bessie M. DeWerff Notary Public.



RECEIVED
 STATE CORPORATION COMMISSION

MAY 06 1985

5-6-85