

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas


WELL PLUGGING RECORD

15-009-15704-0000

Barton County, Sec. 8 Twp. 16 Rge. 12 (E) (W)

Location as "NE/CNW'SW'SW" or footage from lines SW/SE/NE
Lease Owner Harms - Burt Drilling Company
Lease Name Bushnell Well No. 1
Office Address _____
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1-15 1962
Plugging completed 1-23 1962
Reason for abandonment of well or producing formation _____
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well R. L. Lackamp, Jr.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3315 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	207'	None
				5 1/2"	3312'	2595'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug @ 3212'
Top Perforation 3110'

Sanded to 2990' - dumped 5 sks cement - pulled casing - pumped 10 sks Gel Mud into hole - mudded hole to 210' - set 10' rock bridge - mudded hole to 40' - set 10' rock bridge - dumped 10 sks cement

RECEIVED
STATE OF KANSAS
MAP 1962
CONSERVATION DIVISION
Wichita, Kansas
03-09-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Company License # 236
Address Box # 572, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
H. Allan Harms (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. Allan Harms
P.O. Box 488, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6 day of February, 1962

My commission expires 1-20-66

Mary E. Van Pelt
Notary Public.



D R I L L E R S L O G

Company: Harms-Burt Drilling Company SW SE NE Section 8-16-12W
Farm: Bushnell #1 Barton County, Kansas
Commenced: May 16, 1955 Completed: May 25, 1955

Elevation: 1877 KB

0 - 40	Post lime
40 - 285	shale & shells
285 - 305	sand
305 - 470	shale & shells
470 - 790	shale-red bed
790 - 820	anhydrite
820 - 1435	shale & shells
1435 - 1500	lime & shale
1500 - 1590	lime
1590 - 2125	lime & shale
2125 - 2415	shale & lime
2415 - 2735	lime & shale
2735 - 2890	lime
2890 - 2969	lime & shale
2969 - 3010	shale & lime with sand streaks
3010 - 3026	shale & lime
3026 - 3305	lime
3305 - 3311	Conglomerate
3311 - 3315	sand
3315	Total depth

RECEIVED
STATE OF KANSAS COMMISSIONER
MAP 1962
CONSERVATION DIVISION
Wichita, Kansas

Set 207 feet of 8 5/8" casing. Cemented with 175 sacks of common cement with 2% calcium chloride.

Tops:	Anhydrite	-	790
	Heebner	-	2940
	Lansing	-	3038
	Conglomerate	-	3298
	Reagan	-	3312

Ran 5 1/2 inch casing to a depth of 3312'. Cemented with 125 sacks of cement.

A F F I D A V I T

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

I, Allan Harms of the Harms-Burt Drilling Company being first duly sworn on oath state: I have knowledge of the facts, statements and matters herein contained and the same are true and correct.

Allan Harms
Allan Harms

Subscribed and sworn to before me this 8 day of March, 1962.

Helen E. Gearhart
Helen E. Gearhart Notary Public

My commission expires January 22, 1966.