

15-009-03245-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 5 Twp. 16 Rge. 12 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW SE SW

Lease Owner Great Bend Pipe & Supply Company, Inc.

Lease Name Depiesse Well No. 2

Office Address Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed _____ 19__

Application for plugging approved _____ 19__

Plugging commenced 4-14-66 _____ 19__

Plugging completed 4-16-66 _____ 19__

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3288 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	518'	None
				5-1/2"	3276'	1849'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, pumped out bridge, sanded hole to 3250'
and dumped 5 sacks of cement @ 3250' with dump bailer.
Pulled 5 1/2" casing, bailed hole to 325' and dumped 25
sacks of cement. Mudded hole to 30', set rock bridge
and ran 10 sacks of cement to base of cellar.

4-26-66

RECEIVED
STATE CORPORATION COMMISSION
APR 26 1966
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.

Noel J. Knight (employee of owner) or (~~WARRANTED OPERATOR~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of April, 1966

Milton J. Volin

My commission expires May 20, 1968

Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

Wichita, Kansas

15-009-03245-00-00


Company - PHILLIPS & HANSON
 Farm - Depiesse No. 2

SEC. 5 T. 16 R. 12W
 NW 33 SW

Total Depth. 3288
 Comm. 6-26-49 Comp. 7-6-49
 Shot or Treated. 300 gals. acid
 Contractor.
 Issued. 11-26-49

County. Barton

KANSAS



Elevation. _____

Production. 3000 Bbls. Max.

CASING:

8" set \odot 518' w/225 sx.
 5" set \odot 3276' w/100 sx.

Figures indicate Bottom of Formations.

Soil & port rock	30
Shale & shells	70
Shale, shells & sand	450
Shells & shale	500
Red bed	690
Red rock	795
Anhydrite	819
Shale & shells	1170
Shale & salt	1350
Shale & shells	1425
Shale & lime	1690
Lime	1980
Lime & shale	2325
Shale & shells	2450
Shale & lime	2650
Lime & shale	2668
Lime	2720
Lime cherty	2770
Lime	2940
Lime broken	3025
Lime	3288

RECEIVED
 STATE CORPORATE COMMISSION

APR 6 1946

CONSERVATION DIVISION
 Wichita, Kansas

Total Depth

FORMATION TOPS (D.F.)

Heebner	2929
Br. Lime	3018
Lans-K.C.	3026
Arbuckle	3275

D.P. to O.T.D.

Filled up 1000' oil 1st hr. N.W.
 $\frac{1}{2}$ 24 BPH - 300 Gal. acid.