

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-19008-00-01
Spot: SESESE Sec/Twnshp/Rge: 19-23S-14W
330 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: SHEPHERD Well Number: 2
County: STAFFORD Total Vertical Depth: 4094 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S. MAIN
STAFFORD, KS 67578

Conductor Pipe: Size feet: \$133.06
Surface Casing: Size 8.625 feet: 257
Production: Size 5.5 feet: 4090 WITH 140 SX CMT
Liner: Size feet:

Well Type: EOR UIC Docket No: E15604.4 Date/Time to Plug: 02/13/2002 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3650' & 5 SX CMT. 1ST PLUG AT 1000' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/13/2002 2:35 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3815'. PERFS AT 3703, 3710-3778'. SAND TO 3650' & 5 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 1000' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
MAR 06 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2610' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

INVOICED FEB 26 2002
DATE Mar 6-02
INV. NO. 2002061453 AP

Form 213