

1030291

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-20,363-0000

C W/2 SE/4, SEC. 18, T 21 S, R 17 W XX
N SE Corner of
1320 feet from ~~WXX~~ section line
W SE Corner of
1980 feet from ~~WXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9632

Lease Name Prusa Well # 1-18

Operator: ~~Belnorth~~ Internorth
Name & Address P.O. Box 249 P.O. Box 35288 Tulsa 74135
Woodward, OK 73801

County Pawnee

Well Total Depth 2145 69.71 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 837

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 3:30 pm Day: 1 Month: October Year: 19 84

Plugging proposal received from Byron Clawson

(company name) Rockhold (phone) 316-692-2506

were: 4 1/2" set at 2145' PBTD 2139' Perfs at 2042-50

1st plug sand back to 1990' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls

release 8 5/8" rubber plug and pump 150 sx cement

Plugging Proposal Received by Steve Dumont
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:00 pm Day: 1 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 2145' PBTD 2139' Perfs at 2042-50'

1st plug sanded back to 1990' and dumped 4 sx cement on top of sand through bailer

2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

released 8 5/8" rubber plug and pumped an additional 150 sx cement STATE CORPORATION COMMISSION

10-9-84 OCT 09 1984

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 1400' 4 1/2" casing Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(if additional description is necessary, use BACK of this form.)

(if applicable) observe this plugging.

Signed Steve Dumont
(TECHNICIAN)

INVOICED

DATE 10-15-84

INV. NO. 4285