

1 070584

9-7

API NUMBER 15- 145-20,308-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SW NW, SEC. 18, T 21 S, R 17 W/E
3630 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Froetschner Well # 1

Operator: Berexco Inc.
Name & Address 970 Fourth Financial Center
Wichita, KS 67202

County Pawnee 72.64
Well Total Depth 2335 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 372

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Plains Inc. License Number 4072

Address P.O. Box 346, Ness City, KS 67560

Company to plug at: Hour: 4:15 p.m. Day: 7 Month: 9 Year: 19 88

Plugging proposal received from Clint Base

(company name) Plains Inc. (phone) 913-798-3995

were: 5 1/2" at 2334' PBDT 2200' Perfs at 2074-2142'

1st plug pump 3 sx hulls and 20 sx common cement and 50 sx ATL cement.

2nd plug pump 100 sx cement down backside.

RECEIVED
STATE CORPORATION COMMISSION

9-14-88

SEP 14 1988

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations Abandoned by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:45 p.m. Day: 7 Month: 9 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 300 lbs. hulls, 20 sx common cement 2% cc,

and 95 sx Thrifty Mix 2% cc down 5 1/2". Maximum pressure 1000 psi and shut in 600 psi.

2nd plug pumped 80 sx Thrifty Mix cement down 5 1/2" X 8 5/8" annulus. Maximum pressure

100 psi and shut in 0 psi. Approximately 2 sx cement came to surface 100' from well.

Remarks: Used common cement and Thrifty Mix cement by B.J. Titan. No casing recovery.
(If additional description is necessary, use BACK of this form.)

(did / did not) observe this plugging.

Signed Dan Goodrow (TECHNICIAN)

INVOICED
DATE 9-15-88
INV. NO. 22275