

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-145-21,055-0000

NE NW NW, Sec. 26, T 21 S, R 16 W  
330 feet from N/X section line  
990 feet from W/X section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5247

Lease Name Haney Well # 1

Operator: Property Management  
Name & 300 West Douglas, Suite 442  
Address Wichita, KS 67202

County Pawnee

Well Total Depth 3904 feet # 126.88

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 972

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allen Drilling License Number 5418

Address Box 1389, 1105 Walnut, Great Bend, KS 67530

Company to plug at: Hour: 12:00 noon Day: 29 Month: August Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO \_\_\_\_\_

(company name) Allen Drilling (phone) 316-793-5681

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 1020' with 50 sx cement

2nd plug at 540' with 40 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement

Plug water well with 5 sx cement

Signed Steve Rount  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:30 pm Day: 29 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1020' with 50 sx cement, 2nd plug at 540' with

40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to

surface with 10 sx cement, 5th plug to circulate rathole with 15 sx cement,

plug water well with 5 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% CC by Halliburton

Bud Metz went to the well and observed the operation

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 29 1984  
CONSERVATION DIVISION  
Wichita, Kansas

2-29-84

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

INVOICED  
DATE 3-1-84  
INV. NO. 0476

Signed Steve Rount  
(TECHNICIAN)