

1030355

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,174-0000

S/2 NE SW, SEC. 28, T 21 S, R 16 W/EX

1650 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5418

Lease Name Hewson Well # 1-28

Operator: Allen Drilling Company

County Pawnee 128.05

Name & Address P. O. Box 1389

Well Total Depth 3940 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1010

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Allen Drilling Company License Number 5418

Address P. O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 11:00 am Day: 31 Month: December Year: 19 84

Plugging proposal received from Don Carns

(company name) Allen Drilling (phone) 316-793-3582

were: to fill hole with heave mud and spot cement through drill pipe

RECEIVED
STATE CORPORATION COMMISSION

1st plug at 1050' with 50 sx cement

2nd plug at 600' with 25 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 15 sx cement

JAN 09 1985
1-9-85
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:30 pm Day: 31 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1050' with 50 sx cement, 2nd plug at 600' with 25

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to

circulate mouse hole with 15 sx cement

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED

(did not) observe this plugging.

DATE 1-16-85

Signed Steve Durrant (TECHNICIAN)

INV. NO. 6483

FEB 14 1985

12-31