

10-22 4-110033

00-00

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-21,854
160' NE C. of
NW SE NE /4 SEC. 12, 15 S, 18 W
3744 feet from S section line
766 feet from E section line

Operator license# 5127
Operator: Steckline Oil Company
Address: 579 280th Avenue
Hays, Kansas 67601

Lease: Steckline Well # 3
County: Ellis 116.71
Well total depth 3591 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 1160 feet

Aband. oil well , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Quality Well Service License# 31925

Address: 249 E. Beth Dr. - Sterling, Kansas 67579

Company to plug at: Hour: 12:00 P.M. Day: 22 Month: October Year: 1997

Plugging proposal received from: Richard McIntyre

Company: Quality Well Service Phone: 316-727-3410

Were: Ordered 270 sxs 60/40 pozmix with 10% gel and 400# hulls.
Plug while pulling casing.

10-29-97
RECEIVED
OCT 30 1997
PLUGGING DIVISION

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All , Part [], None []

Completed: Hour: 3:45 P.M., Day: 22, Month: October, Year: 1997

Actual plugging report: 8 5/8" at 1160' w/400 sxs. 5 1/2" at 3589' w/125 sxs. Perfs at 3414' - 3416' and 3420' - 3423'. Sanded to 3362' w/5 sxs cement. Shot 5 1/2" casing off at 2000'. Pulled 4 joints 5 1/2" casing and pumped 130 sxs cement with 300# hulls. Pulled to 1200' and pumped 40 sxs cement with 200# hulls. Pulled to 450' and circulated with 65 sxs cement. Pulled rest of 5 1/2" casing - cellar was full of cement. Total of 235 sxs 60/40 pozmix - 10% gel and 500# hulls.

October 23, 1997 - Steckline oil Company ordered and pumped 1 1/2 yards of readimix to top off well.

Remarks: Allied Cementing.
Condition of casing (in hole): GOOD BAD _____ Anhy. plug: YES NO _____
Bottom plug (in place): YES , CALC _____, NO _____ Dakota plug: YES , NO _____
Plugged through TUBING _____, CASING . Elevation: 1990 GL

I did / did not [] observe the plugging.

Roger Moses
(agent)

NO

Form CP-2/3

INVOICED

DATE OCT 30 1997

INV. NO. 49405