

4-061128

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

12-17

API Number: 15-009-24,646-00-00
SW NE NE /4 SEC. 09, 16 S, 12 W
4290 feet from S section line
990 feet from E section line

Operator license# 31560
Operator: Maxwell Operating Co., Inc.
Address: P.O. Box 1213
Hays, Kansas 67601

Lease: Staudinger Well # 1
County: Barton 108.75
Well total depth 3346 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 408 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Discovery Drilling License# 31548
Address: Hays, Kansas 67601

Company to plug at: Hour: 6:00 P.M. Day: 17 Month: December Year: 1997

Plugging proposal received from: Tom Alm

Company: Phone:

Were: Order 145 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour 9:30 P.M., Day: 17, Month: December, Year: 1997

Actual plugging report:
1st. Plug at 800' w/25 sxs. - Anhydrite 785' - 805'.
2nd. Plug at 475' w/60 sxs. - Surface pipe to 408'.
3rd. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING Elevation: 1865 GL

I did [] / did not [X] observe the plugging.

[Signature]
(agent)
DK Form CP-2/3

RECEIVED
KANSAS CORP COM
DEC 22 2 08 PM '97

INVOICED
DATE JAN 06 1998
INV. NO. 49828
12-17 MAR 03 1998

12-22-97