

To: 6 061715
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-18
API NUMBER 15- 009-21,295-00-00

TECHNICIAN'S PLUGGING REPORT

Operator License # 5230

Operator: Petroleum Energy Inc.
Name & Address: 224 East Douglas
Wichita, Ks. 67202

SW _____, SEC 9 _____, T 16 S, R 12 W/E
_____ 990 feet from S section line
_____ 4290 feet from E section line

Lease Name Turgeon Well # 1

County Barton 108.84

Well Total Depth 3349 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 436

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number _____

Address Box 768 Great Bend, Ks. 67530

Company to plug at: Hour: 9:00AM Day: 18 Month: Nov Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers Inc. (phone) _____

were: Order 200 sks 60/40 Poz 6% Gel 3% Cal Cl 5 sks Hulls.

RECEIVED
STATE CORPORATION COMMISSION

DEC 9 1988

12-20-88

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)


Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 11:00AM Day: 18 Month: Nov Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 436' w/250 sks. 5 1/2" set at 3347'

w/125 sks. Open hole 2'. Plugged bottom w/sand and 5 sks cement to 3200'. Shot pipe two times and recovered 2128'. Pumped in 8 5/8" 25 sks cement followed w/ 5 sks Hulls in 175 sks cement w/800 psi.

Remarks: By Halliburton Ran line to 900'
(If additional description is necessary, use BACK of this form.)

INVOICED
did not observe this plugging.

Signed 
(TECHNICIAN)
Gilbert G. Scheck



DATE 1-5-89
INV. NO. 23504