

1 070131

API NUMBER 15- 145-21,182-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NE NW, SEC. 12, T 21 S, R 16 W/EX

4620 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5407

Lease Name Phinney Well # 1

Operator: Hupfer Oil & Gas

County Pawnee 124.12

Name:

Address 3711 Country Lane

Well Total Depth 3819 feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 954

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 3 Month: February Year: 19 86

Plugging proposal received from Mark McCabe

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 3812' Perfs at 3776-80'

1st plug sand back to 3726' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 130 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:00 pm Day: 3 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3726' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" wiper plug and pumped 130 sx cement.

Maximum pressure 700 psi and shut in 600 psi

Remarks: Recovered 2729' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

I (date) 12536 observe this plugging.

DATE FEB 11 1986

RECEIVED
STATE CORPORATION COMMISSION
Dan Jordan
(TECHNICIAN)

INV. NO. 12536

FEB 10 1986 2-10-86

2-3

CONSERVATION DIVISION

FORM CP-2/3
Rev. 01-84