

To: 1080420  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION SE NW NW, SEC. 13, T 21 S, R 16 W/X  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,119-0000  
4290 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050  
Operator: Kelso Casing Pulling bought from/  
Name & Address Alma, Inc.  
3711. Country Lane  
Hays, KS 67601

Lease Name Marlett Well # 1  
County Pawnee 125.94  
Well Total Depth 3875 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 976

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 17 Month: September Year: 19 85

Plugging proposal received from Norman Kelso  
(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 3851' Perfs at 3822-23', 3826', 3827', 3828'  
1st plug sand back to 3770' and dump 5 sx cement on top of sand through bailer  
2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,  
release 8 5/8" rubber plug and pump 150 sx cement

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:15 pm Day: 17 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3790' and dumped 5 sx cement on top  
of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement,  
10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 700 psi and shut in 400 psi

Remarks: Recovered 2800' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

NOTICED  
DATE 9-30-85  
INV. NO. 10292

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 27 1985  
CONSERVATION DIVISION  
Wichita, Kansas

Signed J. A. [Signature]  
(TECHNICIAN)