

11-17-87 15-145-20552-0001

To: 1 120050  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-145-20,552-A  
NE SW NE, SEC. 25, T 21 S, R 16 W/K  
3630 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8778  
Operator: Midwestern Supply Company, Inc.  
Name & Address 300 Patton Road  
Great Bend, KS 67530

Lease Name Fleske (OWWO) Well # 1-B  
County Pawnee 129.51  
Well Total Depth 3985 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 950

Abandoned Oil Well  never produced. Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 17 Month: 11 Year: 19 87

Plugging proposal received from Mark McCabe

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 3980'

1st plug sand back to 3930' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls and 150 sx ATL with 2 sx hulls mixed in the cement.

Plugging Proposal Received by Richard Lacey & Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12 p.m. Day: 17 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3900' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls and 150 sx ATL cement, mixed additional 200 lbs. hulls in ATL cement.

Pumping pressure 200-400 psi. Shut in pressure 0 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
11-19-87  
NOV 19 1987

Remarks: Used ATL cement by Allied. Recovered 3000' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I hereby acknowledge and agree to observe this plugging.

Signed Quentin Rankin  
(TECHNICIAN)

DATE 12-3-87  
INV. NO. 19051