

1060291

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,148 - 0000

SE SE NE, SEC. 22, T 21 S, R 16 W/EK
3120 feet from ~~XXX~~ SE Corner of
330 feet from ~~XXX~~ SE Corner of

TECHNICIAN'S PLUGGING REPORT

Operator License # 5040

Lease Name Buster Well # 1

Operator: Alpine Drilling Co., Inc.

County Pawnee

Name & Address 200 East First, Suite 500

Well Total Depth 3905 126.91 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 984

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor J.W. Drilling Co., Inc. License Number 5137

Address 200 East First, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 12:00 a.m. Day: 2 Month: August Year: 19 84

Plugging proposal received from Walt Coldwater

(company name) J.W. Drilling (phone) 316-263-5705

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3900' with 50 sx cement

2nd plug at 1030' with 50 sx cement

3rd plug at 520' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:45 am Day: 2 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 3900' with 50 sx cement, 2nd plug at 1030' with 50 sx cement, 3rd plug at 520' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

8-6-84

AUG 06 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE 8-14-84

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 3085