

To: 1 050957
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NOV 1 0 1987
API NUMBER 15-145-20,979-0000
150' SE of
SE NW SE, SEC. 22, T 21 S, R 16 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 6039
Operator: L.D. Drilling
Name
Address Rt. 1, Box 183B
Great Bend, KS 67530

1575 feet from S section line
1575 feet from E section line
Lease Name Arnold Well # 1
County Pawnee
Well Total Depth 3875 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 980

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3 p.m. Day: 10 Month: 11 Year: 19 87

Plugging proposal received from Millard Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 3872' Open hole at 3872-75' Elevation 1985'
1st plug pump 400 lbs. hulls and 120 sx ATL cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 10 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3820' and dumped 4 sx cement on top of sand
through bailer,

2nd plug pumped down the 8 5/8" with 400 lbs. hulls and 120 sx ATL cement.

Maximum pressure 500 psi and shut in 300 psi.
RECEIVED
NOV 16 1987
11-16-87
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used ATL cement by Allied. Recovered 1600' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Richard W. Lacy
(TECHNICIAN)

INVOICED

NOV 20 1987

18916