

To: 1 080113 3-18
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 055-20,259-0000
App. C SW, SEC. 18, T 21 S, R 31 W/X

TECHNICIAN'S PLUGGING REPORT

Operator License # 4058
Operator: American Warrior, Inc.
Name & Address: P.O. Box 399
Garden City, KS 67846

1320 feet from S section line
1320 feet from W section line
Hutchinson
Lease Home F.N.B. of Well # 1
County Finney
Well Total Depth 2740 89.05 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 7" feet 353

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage License Number 31524
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8:45 a.m. Day: 18 Month: 3 Year: 19 97

Plugging proposal received from Kevin Wiles

(company name) American Warrior (phone) 316-938-2943

Work: 4 1/2" at 2736' w/100 sx cement, PBD 2736', Perfs at 2694-99'

1st plug pump 200 lbs. hulls and 20 sx cement,

2nd plug shoot casing and pump 70 sx cement,

3rd plug shoot casing and pump 40 sx cement,

4th plug pull up to 380' and pump 40 sx cement, 5th plug top off with 10 sx cement.

Plugging Proposal Received by Kevin Strube (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 18 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 20 sx cement. Well on vacuum.

Displaced past perforations. Maximum pressure 1200 psi and shut in 600 psi.

2nd plug pumped 300 lbs. hulls and 20 sx cement,

3rd plug shot casing at 1400' and pumped 70 sx cement, displaced to 1000'. Maximum pressure 300 psi, 2 bbl. per minute.

4th plug shot casing at 721' and pulled one joint up to 690'. Pumped 40 sx cement.

5th plug pulled up to 380' and pumped 40 sx cement. 6th plug pulled out of hole and topped off

Remarks: Used 65/35 Pozmix 6% gel by Halliburton. Recovered 721' of 4 1/2" casing. with 10 sx emt.

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-26-97

Signed Kevin Strube (TECHNICIAN)

INV. NO. 47817

RECEIVED
KANSAS CORP COM.
1997 MAR 26 10 12 33

3-26-97

3-18