

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-145-20, 957-0000

LEASE NAME Powers

WELL NUMBER #1

990 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 14 TWP. 21 RGE. 16 (E) or (W)

COUNTY Pawnee

Date Well Completed 5-2-82

Plugging Commenced 1-4-92

Plugging Completed 1-4-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Hupfer Operating Inc.

ADDRESS 25th & Vine St, Hays, KS 67601

PHONE# (913) 628-8666 OPERATORS LICENSE NO. 30380

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-2-92 (date)

by Steve Middleton - KCC Dist #1 Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3782 Bottom 3786 T.D. 3864

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	968'	----
				5 1/2	3862'	2116

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pushed plug to 3780' - Sandback 3730' & Dump bail 5 sx cement @ 3730'/Lay Down 2116' 5 1/2 Casing & plug from top-used 300 lbs. Hulls-10 sx Gell-50sx 60/40 poz 6% Gell-5sx Gell-100 lbs. Hulls-8 5/8 wiper plug-150sx 60/40 poz 6% Gell started plugging @ 8:00 AM & plugging completed @ 9:00 am on 1-4-92-Duane Rankin, KCC Rep. (If additional description is necessary, use BACK of this form.) was present.

Name of Plugging Contractor Pipe Recovery Inc. License No. 30752 JED
Address P.O. Box 7, Great Bend, KS 67530 KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hupfer Operating Inc. JAN 2 2 1992

STATE OF Kansas COUNTY OF Ellis, ss.

Dennis D. Hupfer (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dennis D. Hupfer
(Address) 25th & Vine St, Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 20 day of Jan, 19 92

Agnes Wasinger
Notary Public

