

To: 1 120668  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
209 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1-4  
API NUMBER 15- 145-20,957-0000 15 P

NE SE NE, SEC. 14, T 21 S, R 16 W/EK

3630 feet from S section line

660 feet from E section line

Lease Name Powers Well # 1

County Pawnee 125.58

Well Total Depth 3864 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 968

TECHNICIAN'S PLUGGING REPORT  
Operator License # 30380

Operator: Hupfer Operations, Inc.  
Name &  
Address 25th & Vine  
Hays, KS 67601

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pipe Recovery Inc. License Number 30752

Address P.O. Box 7, Great Bend, KS 67530

Company to plug at: Hour: 8 a.m. Day: 4 Month: 1 Year: 19 92

Plugging proposal received from Rick Davis

(company name) Pipe Recovery Inc. (phone) 316-793-3922

were: 5 1/2" at 3862' w/150 sx cement, PBSD 3844', Perfs at 3782-86, 3827-29, 3847-49'  
1st plug sand back to 3725' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump in 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 5 sx gel,  
100 lbs. hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:45 a.m. Day: 4 Month: 1 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3730' and dumped 5 sx cement on  
top of sand through bailer,  
2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 5  
sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.  
Pumping pressure 0-900 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2123' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
I (did) ~~not~~ observe this plugging. 1-791  
DATE 1-17-92 JAN 7 1992 Signed \_\_\_\_\_  
34372

Duane Rankin  
(TECHNICIAN)

INV. NO. 34372  
1-4-92  
CONSERVATION DIVISION  
WICHITA, KS