

1 030612

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,230-0000

SW NE NW, SEC. 14, T 21 S, R 16 W/E

4290 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5407

Lease Name Bailey Well # 1

Operator: Hupfer Oil & Gas

County Pawnee

Name & Address

3711 Country Lane

Well Total Depth 3900 Arbuckle 126.75 feet

Hays, KS 67601

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 999

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor H-30, Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 11:00 pm Day: 11 Month: December Year: 19 85

Plugging proposal received from Rick Davis

(company name) H-30, Inc. (phone) 316-263-2043

\_\_\_\_\_ Elevation 1965

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 978

1st plug in the Arbuckle with 40 sx cement if in 50' or more

2nd plug 30' below the base of the surface pipe with 50 sx cement

3rd plug at 420' with 25 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 1:30 am Day: 12 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 3830' with 40 sx cement, 2nd plug at 1020' with 50 sx

cement, 3rd plug at 420' with 25 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15

sx cement. Plugged water well with 10 sx cement

Remarks: Used 60/40 Pozmix 6% gel by Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE DEC 20 1985

INV. NO. 11670

STATE CORP

Signed Steve Durrant  
(TECHNICIAN)

DEC 20 1985

12-20-85

CON. DIVISION

CARD MUST BE TYPED

State of Kansas  
NOTICE OF INTENTION TO DRILL  
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: Nov. 23 1985  
month day year

API Number 15- 145-21,230-0000

OPERATOR: License # 5407  
Name Hupfer Oil & Gas  
Address 3711 Country Lane  
City/State/Zip Hays, Kansas 67601  
Contact Person Dennis D. Hupfer  
Phone 913-628-8666

SW. NE. NW Sec 14, Twp 21, S. Rge 16.  East  West  
(location)  
4290 Ft North from Southeast Corner of Section  
3630 Ft West from Southeast Corner of Section  
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5107  
Name H-30, Inc.  
City/State Wichita, Kansas 67202

Nearest lease or unit boundary line 990 feet.  
County Pawnee  
Lease Name Bailey Well# 1  
Domestic well within 330 feet:  yes  no  
Municipal well within one mile:  yes  no

Well Drilled For: Well Class: Type Equipment:  
 Oil  Swd  Infield  Mud Rotary  
 Gas  Inj  Pool Ext.  Air Rotary  
 DWFO  Expl  Wildcat  Cable

Depth to Bottom of fresh water 60 feet  
Lowest usable water formation Cheyenne  
Depth to Bottom of usable water 215 feet  
Surface pipe by Alternate: 1  2   
Surface pipe to be set 980 feet  
Conductor pipe if any required N/A feet  
Ground surface elevation 1965 feet MSI.  
This Authorization Expires 5-2-86

If DWFO: old well info as follows:

Operator  
Well Name  
Lump Date Old Total Depth  
Projected Total Depth 3850 feet  
Projected Formation at TD Arbuckle  
Expected Producing Formations Arbuckle

Approved By [Signature] 11-7-85  
11-7-85 [Signature]

Nov. 6, 85. Signature of Operator or Agent [Signature] Dennis D. Hupfer Title President Form C-1 4/84

980' of 8 3/8" on 12/4/85

PUSHER Rick Davis  
TD 3900 FORMATION Arb.  
SURFACE PIPE 8 3/8" @ 999'  
ANHYDRITE 978 ELEVATION 1965  
STARTING TIME & DATE 1:30 Am 12-12-85  
COMPLETION TIME & DATE 3:30  
1st PLUG @ Arbuckle FT. W/ 4 3/4" SX  
2nd PLUG @ 30' SURFACE FT. W/ 50 SX  
3rd PLUG @ 420 FT. W/ 4 3/4" SX  
4th PLUG @ 5 1/2" FT. W/ 5 1/2" SX  
RAT HOLE CIRCULATED W/ 10 SX  
MOUSE HOLE CIRCULATED W/ SX  
WATER WELL PLUGGED W/ SX  
CEMENT COMPANY Haver's  
TECHNICIAN SSO  
60/40 @ 969e  
W.O. @ 910  
HOP

STATE CORP. ...  
DEC 20 1985  
COMPLETION BY ...  
Wichita, Kansas