

15.145.21233-0000

12-5

1 070625

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 12/20/85

NW NE SE, SEC. 14, T 21 S, R 16 W/K

2310 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5407

Lease Name Powers "A" Well # 1

Operator: Hupfer Oil & Gas

County Pawnee 126.75

Name & Address 25th & Vine Street

Well Total Depth 3900 feet

Hays, KS 67601

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 994

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2:30 p.m. Day: 5 Month: 12 Year: 19 88

Plugging proposal received from Clay Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 1st plug sand back to 3750' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release plug
and pump 120 sx cement

RECEIVED
STATE CORPORATION COMMISSION
DEC 9 1988

12-9-88

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:30 p.m. Day: 5 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3750' and dumped 5 sx cement on top of sand through bailer.

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 120 sx cement.

Maximum pressure 600 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2000' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 12-12-88

Signed Dan Horkow (TECHNICIAN)

INV. NO. 23318

15-145.21233-0000

GREAT GUNSSonic Cement
Bond Log

FILING NO.	COMPANY HUPFER OIL AND GAS		
	WELL POWERS 'A' NO. 1		
RECEIVED STATE CORPORATION COMMISSION NOV 21 1985 CONSERVATION DIVISION Wichita, Kansas	FIELD		
	COUNTY	PAWNEE	STATE KANSAS
	Location	NW-NE-SE	
		Twp. 21S	Rge. 16W
Permanent Datum	G.L.	Elev 1970	Elev: K.B. 1975
Log Measured From	K.B.	5 Ft. Above Perm. Datum	D.F.
Drilling Measured From	K.B.		G.L. 1970
Run No.	ONE		
Date & Time Survey	12-27-85	5:30	P.M.
Date & Time Cementing	12-20-85		
Type Cementing Operation	PRIMARY		
Depth Driller	3900		
Depth Logger	3878		
Logged Interval	3871	to 3180	to
Casing Driller		@ 5 1/2	@
Float Collar—D.V. Tool			
Squeeze Depth			
Amount & Type Cement			
Amount & Type Admix			
Type Fluid in Hole	WATER		
Fluid Level	FULL		
Salinity PPM Cl			
Weight lb/gal—Vis			
Approx. Logged Cem Top	3324		
Calculated Cement Top			
Max. Hole Temperature	114°	F	F
Tool No.			
Spacing Recorded	4'		
Equipment—Location	44	G.B.	
Recorded by	K. SMITH		
Witnessed by			