

1121091

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 145-21,033-0000

SE NE NE, SEC. 14, T 21 S, R 16 W/E

4290 feet from S section line

330 feet from E section line

12-13

TECHNICIAN'S PLUGGING REPORT

Operator License # 30108

Lease Name Powers Well # 2

Pawnee

County

Operator: Sterling Oil Company, Inc.

Name:

Address P.O. Box 306

Well Total Depth 3898 126.69 feet

Sterling, KS 67579

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 968

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor DS&W Well Servicing License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 1:30 p.m. Day: 13 Month: 12 Year: 19 95

Plugging proposal received from Kent Strube

(company name) DS&W Well Servicing (phone) 316-587-3361

logs: 5 1/2" at 3898' w/125 sx cement, PBSD 3864', Perfs at 3854-58, 3837-42'

1st plug sand back to 3785' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:30 p.m. Day: 13 Month: 12 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3785' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped in 8.5/8" surface casing with 300 lbs. hulls, 10 sx gel, 150 sx cement, 10 sx gel, 100 lbs. hulls, released 8.5/8" wiper plug and pumped 150 sx cement.

Pumping pressure 0-800 psi and shut in 400 psi.

DEC 20 1995

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1884' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

(All) observe this plugging.

DATE JAN 09 1996

Signed Duane Rankin (TECHNICIAN)

INV. NO. 44467