

1051939

7-29

145-21,429-0000

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 100' E of  
SW SE, SEC. 17, T 21 S, R 16 W/E  
660 feet from S section line  
1880 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5418  
Operator: Allen Drilling Company  
Name: P.O. Box 1389  
Address: Great Bend, KS 67530

Lease Name Giessel Well # 1  
County Pawnee 124.94  
Well Total Depth 3875 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 1040

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Allen Drilling Company License Number 5418  
Address P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 6 a.m. Day: 29 Month: 7 Year: 19 95

Plugging proposal received from Marvin Petz

(company name) Allen Drilling Company (phone) 316-793-3582

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1014'

1st plug at 3815' with 50.sx cement, 2nd plug at 1070' with 50 sx cement,  
3rd plug at 300' with 40 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:30 a.m. Day: 29 Month: 7 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug at 3815' with 50 sx cement,  
2nd plug at 1070' with 50 sx cement,  
3rd plug at 300' with 40 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

8-3-95 AUG 03 1995

CONSULTATION DIVISION

Remarks: Used 60/40 Pozmix 6% gel by Allied.

INVOICED (If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

DATE 8-7-95

Signed Richard M. Lacey (TECHNICIAN)

INV. NO. 43250

7-29

EFFECTIVE DATE: 7-23-95 DISTRICT # 1 SSA7 Yes No

State of Kansas NOTICE OF INTENTION TO DRILL 145-21,429

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date July 17, 1995 month day year

Spot 100' E of SW SE Sec 17 Twp 21 S Rg 16 X West

OPERATOR: License # 5418 Name: ALLEN DRILLING COMPANY Address: P.O. Box 1389 City/State/Zip: Great Bend, KS 67530 Contact Person: Dixon Allen Phone: 316/793-3582 FAX: 316/793-5877

660 feet from South / North line of Section 1880 feet from East / West line of Section IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side) County: Pawnee Lease Name: GIESSEL Well #: 1 Field Name:

CONTRACTOR: License #: 5418 Name: ALLEN DRILLING COMPANY

Is this a Prorated/Spaced Field? yes no X

Well Drilled For: Well Class: Type Equipment: X Oil Enh Rec X Infield X Mud Rotary X Gas Storage Pool Ext Air Rotary OWWO Disposal Wildcat Cable Seismic # of Holes Other

Target Formation(s): Nearest lease or unit boundary: 660 Ground Surface Elevation: 1994 feet MSL

If OWWO: old well information as follows: Operator: N/A Well Name: Comp. Date: Old Total Depth:

Water well within one-quarter mile: yes no Public water supply well within one mile: yes no Depth to bottom of fresh water: 150 180 Depth to bottom of usable water: 225 240 Surface Pipe by Alternate: X 1 2 Length of Surface Pipe Planned to be set: 1020 Length of Conductor pipe required: Projected Total Depth: 3900 Formation at Total Depth: Arbuckle Water Source for Drilling Operations: X well farm pond other

Directional, Deviated or Horizontal wellbore? yes X no

DWR Permit #: Will Cores Be Taken? If yes, proposed zone:

Bottom Hole Location: Exp. 1/18/96

260' Alt. STATE CORPORATION COMMISSION RECEIVED AUG 03 1995

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

15.145.21429-0000

CONSERVATION DIVISION WICHITA, KANSAS

Pusher Marvin Petz

SPUD DATE 7/21/95 INIT. SP

LENGTH SURFACE PLANNED 1020 +

RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 5 1/2 @ 1040 CONDUCTOR ANHYDRITE T- B-1014 ELEVATION

TD 3825 FORMATION Arbuckle

RAN PIPE @ DV TOOL ALT II DONE SX Y N

Arbuckle Plug @ 3875 Ft. W/ 50 SX

Hug./Council @ Ft. W/ SX

Anhydrite Base @ 1020 Ft. W/ 50 SX

1/2 Base Anhy. @ Ft. W/ SX

1/2, 1/2 Plug @ Ft. W/ SX

Bottom Surface @ 300 Ft. W/ 40 SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX

WATER WELL SX (Irr. Well Pond Hauling)

TECHNICIAN R.L DATE 7-27-95

TYPE OF CEMENT 60/40 per 6/6/95

STARTING TIME 6:30 (AM/PM) DATE 7-29-95

COMPLETION TIME 10:30 (AM/PM) DATE 7-29-95

CEMENT COMPANY Allied