

5-2

To: J-120417

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-21,223-0000

S/2 N/2 NW, SEC. 23, T 21 S, R 16 W/E

4290 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9354

Lease Name Buster Well # 1B

Operator: Central Energy

County Pawnee 127.73

Name & Address Box 38, RR 1

Well Total Depth 3930 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 985

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Gressel Corporation License Number 5822

Address Box 322, Haysville, KS 67060

Company to plug at: Hour: 1 p.m. Day: 2 Month: 5 Year: 19 90

Plugging proposal received from Todd Allam

(company name) Gressel Corporation (phone) 316-522-1560

were: 5 1/2" at 3924' PBTB 3924' Perfs at 3768-76, 3782-88'

1st plug sand back to 3720' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 15 sx gel, 50 sx cement, 5 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 2 Month: 5 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 3720' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 15 sx gel, 50 sx cement, 5 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Maximum pressure 800 psi and shut in 400 psi.

STATE CORP 5-9-90

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2900' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-16-90

Signed Duane Rankin (TECHNICIAN)

INV. NO. 28151