

To: 1 120105  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

6-17-88 180  
API NUMBER 15-055-20,799-0000  
C SE SE SE SEC. 28, T 21 S, R 31 W/4

TECHNICIAN'S PLUGGING REPORT

Operator License # 4779

330 feet from S section line  
330 feet from E section line  
Lease Name Doll Well # 28-1

Operator: North American Resources Company  
Name & Address: 16 East Granite  
Butte, MT 59701

County Finney 162.50  
Well Total Depth 5000 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 465

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Cheyenne Drilling Inc. License Number 5382  
Address Box 916, Garden City, KS 67846

Company to plug at: Hour: 3 p.m. Day: 17 Month: 6 Year: 19 88

Plugging proposal received from Jack Pepper  
(company name) Cheyenne Drilling, Inc. (phone) 316-277-2062

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2155-75'  
1st plug at base of Hugoton with 100 sx cement, 2nd plug at 2150' with 50 sx cement,  
3rd plug at 1300' with 100 sx cement, 4th plug at 500' with 40 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 6 p.m. Day: 17 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 2980' with 100 sx cement,  
2nd plug at 2150' with 50 sx cement,  
3rd plug at 1300' with 100 sx cement,  
4th plug at 500' with 50 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(If additional description is necessary, use BACK of this form.)  
CONSERVATION DIVISION  
Wichita, Kansas

observe this plugging.

INVOICED

Signed Duane Rankin (TECHNICIAN)

DATE 7-15-88  
INV. NO. 21352

6-22-88  
RECEIVED  
STATE CORPORATION COMMISSION  
JUN 22 1988

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date May 1988 month day year

API Number 15-055-20,799-0000

OPERATOR: License # 4779 Name North American Resources Company Address 16 East Granite City/State/Zip Butte, MT, 59701 Contact Person Leo A. Heath Phone (406) 723-5421

C. SE SE SE Sec. 28. Twp. 21 S, Rg. 31 East X West 330 Ft. from South Line of Section 330 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5382 Name Cheyenne Drilling, Inc. City/State Garden City, KS

Nearest lease or unit boundary line 330 feet County Finney

Well Drilled For: Well Class: Type Equipment: X Oil SWD Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl X Wildcat Cable

Lease Name Dall Well # 2B-1 Ground surface elevation 289.1 feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no

If OWWO: old well info as follows:

Depth to bottom of fresh water 200! Depth to bottom of usable water 1300! Surface pipe by Alternate: 1 2 Surface pipe planned to be set 450! Conductor pipe required No Projected Total Depth 5000 feet Formation Mississippian

Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq, plus eventually plugging hole to KCC specifications. Date 5/16/88 Signature of Operator or Agent Title Mgr. Eng. and Oper.

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 220 feet per Alt. This Authorization Expires 11-24-88 Approved By 7-15-88

EFFECTIVE DATE: 5-29-88 Handwritten note: Hand water

Spud 3:PM 6/8/88

450' 8 7/8 SP

C SE SE SE Sec. 28 Twp. 21 S, Rg. 31 East X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug depth, feet depth with, and Class 'G' cement. Includes entries for 1st through 5th plugs and a Rathole.

Vertical list of well details: PUSHER Job Peppan, TD 5000, SURFACE PIPE 8 7/8 @ 465, ANHYDRITE 2155-15 ELEVATION 4-17-88, STARTING TIME & DATE 3:00 PM, COMPLETION TIME & DATE 6-17-88 6:00 PM, 1st PLUG @ 2150 FT. W/ 50 SX, 2nd PLUG @ 1300 FT. W/ 100 SX, 3rd PLUG @ 500 FT. W/ 40 SX, 4th PLUG @ 40 FT. W/ 15 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ SX, CEMENT COMPANY Rankin, TECHNICIAN Rankin, 60-40-670

Loggins at Present 6-16-88 RECEIVED STATE CORPORATION COMMISSION JUN 22 1988 CONSERVATION DIVISION Wichita, Kansas