

7-3

To: 6 062180
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009-04828-0000
SW, SEC. 25, T 19 S, R 14 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5614

Operator: Hutchinson Oil Co.
Name & Address: 105 S. Broadway
Wichita, Ks. 67202

2310 feet from S section line
2970 feet from E section line

Lease Name Hiss Well # 2

County Barton 110.50

Well Total Depth P.B. 2350 TD 3400 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 790

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling In. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 10:00AM 3 Day: 3 Month: July Year: 19 90

Plugging proposal received from Bill Fouls

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2943

were: Order 200 sks 60/40 poz 8% gel 5 sks hulls.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:55AM Day: 3 Month: July Year: 19 90

ACTUAL PLUGGING REPORT 8 5/8 set at 790 w/cwc. 4 1/2 set at 3400 w/150 sks.

Top perf at 2260. Plugged bottom w/sand and 4 sks cement to 2200.

Shot pipe one time and recovered 1600. Pumped in 8 5/8 25 sks cement followed w/5 sk hulls in 175 sks cement w/700 psi.

RECEIVED
STATE CORPORATION COMMISSION

7-9-90

JUL 9 1990

Remarks: Allied.

(If additional description is necessary, use BACK of this report.)

INVOICED

DATE 7-17-90

INV. NO. 28599

7-3

Signed Gilbert G. Scheck
(TECHNICIAN)