STATE OF KANSAS STATE CORPORATION COMMISSION 200 Colorado Derby Building Wichita, Kansas 67202

## WELL PLUGGING RECORD K.A.R.-82-3-117

API NUMBER: 15-145-20,979-0000


EASE NAME Arnol	EASE N	AME	Arnol
-----------------	--------	-----	-------

TYPE OR PRINT NOTICE: Fill out completely office within 30 days.

FENSE NYWE	MINOIG	
WELL NUMBER	#1	

Ft. from S Section Line and return to Cons. Div. Ft. from E Section Line
150' SE of SE NW SE LEASE OPERATOR L.D. Drilling, Inc. SEC. 22 TWP.21 RGE.16W (E)or(W) R.R. #1 Box 183B Great Bend, Kansas 67530 COUNTY Pawnee PHONE (316) 793-3051 OPERATORS LICENSE NO. 6039 Date Well Completed Character of Well Oil Plugging Commenced11-5-87 Plugging Completed11-10-87 (OII, Gas, D&A, SWD, Input, Water Supply Well) Did you notify the KCC District Office prior to plugging this well? Yes Which KCC Office did you notify? \_\_\_\_\_ Dist. #1 Dodge City, Kansas Is ACO-1 filed?\_\_\_\_\_\_If not, is well log attached? Producing Formation Depth to Top Bottom T.D. 3875 Show depth and thickness of all water, oil and gas formations. OIL, GAS OR WATER RECORDS CASING RECORD Formation From To Size Put In Pulled out 980' 8-5/8" none 3872 1610' Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand to 3750' and 4 sacks cement. Shot pipe @2515', 2310', 1805', 1721', 1610', pulled a total of 38 joints of 4-1/2" casing. Plugged surface with 4 sacks hulls and 120 sacks econolite. Plugging Complete.
(If additional description is necessary, use BACK of this form.) Name of Plugging Contractor Kelso CAsing Pulling, Inc. License No. 6050 Address P.O. Box 347 Chase, Kansas 67524 COUNTY OF Rice STATE OF Kansas Mike Kelso Vice-President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that ? the same are true and correct, so help me God. (Signature) Make (Address) Box 347 Chase, Kansas 67524 SUBSCRIBED AND SWORN TO before me this 17th day of November ,1987

My Commission Expires:



NOV 1 9 1987 . 11-19-8

25/FIVED

Form CP-4

CONSERVATION DIVISION Sed 07-86 Wichita, Kansas

Kan-Go, Inc./Reed #1 Arnold, Larned Pool 150' SE of SE NW SE Sec. 22-21-16W Pawnee County, Kansas

aPI # 15-145-20, 979

Following is data pertaining to this well:

OPERATOR:
CONTRACTOR:
DRILLING COMMENCED:
UNDER SURFACE:
DRILLING COMPLETED:
SURFACE CASING:
PRODUCTION CASING:
ROTARY TOTAL DEPTH:
LOG TOTAL DEPTH:
ELECTRICAL SURVEYS:
DRILLSTEM TESTS:
DRILLING MUD:
PRODUCTION:
MEASUREMENTS:
ELEVATION:

Kan-Go, Inc./Reed
H-30 Drilling Rig #2
6-30-82
7-2-82
7-7-82
8-5/8" at 980' w/450 sx.
4½ at 3872 w/100 sx.
3875'
3869'
Radiation Guard & C.D.-Welex
1-Western Testers
Starch-Davis Mud
Arbuckle-OH
Kelly Bushing
1985'

## DRILLING SUPERVISION

One foot drilling time was kept from 3300° to a Rotary Total Depth of 3875°. Ten foot samples were kept from 3300° to 3875°. Samples were microscopically examined from 3300° to 3875°. Drilling was supervised by Geologist from 3480° to 3875°.

RECEIVED STATE CORPORATION COMMISSION

OCT 3 O 1987

CONSERVATION DIVISION Wichita, Kansas